

Declaration of Conformity

In Accordance with ANSI/ISEA 125-2014 and ANSI/ASSP Z359.7-2019



Alexander Andrew, Inc. 1306 S. Alameda St Compton, CA 90221 (800) 719-4619

Declaration #

B0823164

Declaration Date

8/23/2021

Tested Item #

7073BSM

Contractor+ 3D Construction Belted FBH, MB Chest/TB
Legs, Dual-size Small/Med

Additional Items Conforming Under this Declaration:

7073BLX 7074BSM 7073BDS/M

7073B2X 7074BLX 7073BDL/X

7073B3X 7074B2X

Alexander Andrew, Inc. declares that the product(s) listed above is in conformity with
the requirements of the following product standard(s):

ANSI Z359.11-2021

Conformity Assessment Method in accordance with ANSI/ISEA 125-2014

Level 1

Level 2

Level 3

Level 1: FallTech Lab
Outside the Scope of
ISO/IEC Standard 17025:2005

Level 2: FallTech Lab
Within the Scope of
ISO/IEC Standard 17025:2005

Level 3: Independent 3rd Party Lab
accredited to
ISO/IEC Standard 17025:2005

Supporting
Documentation

PC-2304

Authorized Signature

Name

Zachary Winters

Title

Engineering Manager

Date

8/23/2021



International Accreditation Service, Inc
3060 Saturn St, Ste 100
Brea, CA 92821 +1 562-364-8201

FallTech Lab - TL-594
ISO/IEC 17025:2017
Alexander Andrew Inc dba FallTech

FallTech Test Report

Test Report No.	PC-2304	Rpt. Date	8/19/2021	Rpt. Rev		Rev Date	
Report Prepared For	FallTech						
Initiated By	Dan Redden	Test Specification(s)	ANSI Z359.11-2021: 4.3.5, 4.3.3, 4.3.4, 4.3.6				
Part No.	7073BSM	Part No. Revision	G				
Part Description	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med						
Test Request No.	PC-2304	Date Complete	8/18/2021				
Test Operator(s)	Yesbet Sierra / Jay Sponholz						

Material/Sample Identification

Sample ID	Description
289575	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289589	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289565	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289605	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289573	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289560	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289593	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289555	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289558	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289603	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289624	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289541	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289551	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289566	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med
289581	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med

Test Summary

Test Specification	Test Criteria	Test Result	Pass/Fail	
ANSI Z359.11-2021 4.3.5	Static Strength (Dorsal D-ring)	3600 Lbf \geq 1 Minute	3648.7 Lbf	Pass
	Static Strength (Dorsal D-ring)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Adjuster Slippage	Slippage \leq 1"	0.0"	Pass
	Tear Distance (Buckle)	Shall Not Tear a Distance > 1" or Adjacent Eyelet	Did Not Tear Through	Pass
	Tearing	Straps Shall Not Show Any Signs of Tearing	Did Not Tear	Pass



FallTech Test Report

Test Report No.	PC-2304	Rpt. Date	8/19/2021	Rpt. Rev		Rev Date	
Report Prepared For	FallTech						
Initiated By	Dan Redden	Test Specification(s)	ANSI Z359.11-2021: 4.3.5, 4.3.3, 4.3.4, 4.3.6				
Part No.	7073BSM	Part No. Revision	G				
Part Description	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med						
Test Request No.	PC-2304	Date Complete	8/18/2021				

Test Summary (Continued)

Test Specification	Test Criteria	Test Result	Pass/Fail	
ANSI Z359.11-2021 4.3.5	Static Strength (Dorsal D-ring)	3600 Lbf \geq 1 Minute	3632.0 Lbf	Pass
	Static Strength (Dorsal D-ring)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Adjuster Slippage	Slippage \leq 1"	0.0"	Pass
	Tear Distance (Buckle)	Shall Not Tear a Distance > 1" or Adjacent Eyelet	Did Not Tear Through	Pass
	Tearing	Straps Shall Not Show Any Signs of Tearing	Did Not Tear	Pass
ANSI Z359.11-2021 4.3.5	Static Strength (Dorsal D-ring)	3600 Lbf \geq 1 Minute	3635.5 Lbf	Pass
	Static Strength (Dorsal D-ring)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Adjuster Slippage	Slippage \leq 1"	0.0"	Pass
	Tear Distance (Buckle)	Shall Not Tear a Distance > 1" or Adjacent Eyelet	Did Not Tear Through	Pass
	Tearing	Straps Shall Not Show Any Signs of Tearing	Did Not Tear	Pass
ANSI Z359.11-2021 4.3.5	Static Strength (Side D-rings)	3600 Lbf \geq 1 Minute	3646.0 Lbf	Pass
	Static Strength (Side D-rings)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Adjuster Slippage	Slippage \leq 1"	0.0"	Pass
	Tear Distance (Buckle)	Shall Not Tear a Distance > 1" or Adjacent Eyelet	Did Not Tear Through	Pass
	Tearing	Straps Shall Not Show Any Signs of Tearing	Did Not Tear	Pass
ANSI Z359.11-2021 4.3.5	Static Strength (Side D-rings)	3600 Lbf \geq 1 Minute	3636.1 Lbf	Pass
	Static Strength (Side D-rings)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Adjuster Slippage	Slippage \leq 1"	0.0"	Pass
	Tear Distance (Buckle)	Shall Not Tear a Distance > 1" or Adjacent Eyelet	Did Not Tear Through	Pass
	Tearing	Straps Shall Not Show Any Signs of Tearing	Did Not Tear	Pass

FallTech Test Report

Test Report No.	PC-2304	Rpt. Date	8/19/2021	Rpt. Rev		Rev Date	
Report Prepared For	FallTech						
Initiated By	Dan Redden	Test Specification(s)	ANSI Z359.11-2021: 4.3.5, 4.3.3, 4.3.4, 4.3.6				
Part No.	7073BSM	Part No. Revision	G				
Part Description	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med						
Test Request No.	PC-2304	Date Complete	8/18/2021				

Test Summary (Continued)

Test Specification	Test Criteria	Test Result	Pass/Fail	
ANSI Z359.11-2021 4.3.5	Static Strength (Side D-rings)	3600 Lbf \geq 1 Minute	3641.7 Lbf	Pass
	Static Strength (Side D-rings)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Adjuster Slippage	Slippage \leq 1"	0.0"	Pass
	Tear Distance (Buckle)	Shall Not Tear a Distance > 1" or Adjacent Eyelet	Did Not Tear Through	Pass
	Tearing	Straps Shall Not Show Any Signs of Tearing	Did Not Tear	Pass
ANSI Z359.11-2021 4.3.3	Dynamic Performance Dorsal D-ring (Feet First)	Peak Impact Load \geq 3600 Lbf	5080.3 Lbf	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Remain Suspended for \geq 5 Minutes	5 Minutes	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Angle at Rest \leq 30°	1.1°	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Harness Stretch Shall Not Exceed 18"	10.5"	Pass
ANSI Z359.11-2021 4.3.3	Dynamic Performance Dorsal D-ring (Feet First)	Peak Impact Load \geq 3600 Lbf	4434.3 Lbf	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Remain Suspended for \geq 5 Minutes	5 Minutes	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Angle at Rest \leq 30°	1.2°	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Harness Stretch Shall Not Exceed 18"	10.3"	Pass

FallTech Test Report

Test Report No.	PC-2304	Rpt. Date	8/19/2021	Rpt. Rev		Rev Date	
Report Prepared For	FallTech						
Initiated By	Dan Redden	Test Specification(s)	ANSI Z359.11-2021: 4.3.5, 4.3.3, 4.3.4, 4.3.6				
Part No.	7073BSM	Part No. Revision	G				
Part Description	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med						
Test Request No.	PC-2304	Date Complete	8/18/2021				

Test Summary (Continued)

Test Specification	Test Criteria	Test Result	Pass/Fail	
ANSI Z359.11-2021 4.3.3	Dynamic Performance Dorsal D-ring (Feet First)	Peak Impact Load ≥ 3600 Lbf	4690.8 Lbf	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Remain Suspended for ≥ 5 Minutes	5 Minutes	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Angle at Rest ≤ 30°	1.8°	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
	Dynamic Performance Dorsal D-ring (Feet First)	Harness Stretch Shall Not Exceed 18"	9.9"	Pass
ANSI Z359.11-2021 4.3.4	Dynamic Performance Dorsal D-ring (Head First)	Peak Impact ≥ 3,600 Lbf or 72" Free Fall	72" Free fall 3173.0 Lbf	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Remain Suspended for ≥ 5 Minutes	5 Minutes	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Angle at Rest ≤ 30°	7.1°	Pass
	Dynamic Performance Dorsal D-ring (Head First)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
ANSI Z359.11-2021 4.3.4	Dynamic Performance Dorsal D-ring (Head First)	Peak Impact ≥ 3,600 Lbf or 72" Free Fall	72" Free fall 1848.7 Lbf	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Remain Suspended for ≥ 5 Minutes	5 Minutes	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Angle at Rest ≤ 30°	2.6°	Pass
	Dynamic Performance Dorsal D-ring (Head First)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass

FallTech Test Report

Test Report No.	PC-2304	Rpt. Date	8/19/2021	Rpt. Rev		Rev Date	
Report Prepared For	FallTech						
Initiated By	Dan Redden	Test Specification(s)	ANSI Z359.11-2021: 4.3.5, 4.3.3, 4.3.4, 4.3.6				
Part No.	7073BSM	Part No. Revision	G				
Part Description	Contractor+ 3D Construction Belted FBH, MB Chest/TB Legs, Dual-size Small/Med						
Test Request No.	PC-2304	Date Complete	8/18/2021				


Test Summary (Continued)

Test Specification	Test Criteria		Test Result	Pass/Fail
ANSI Z359.11-2021 4.3.4	Dynamic Performance Dorsal D-ring (Head First)	Peak Impact \geq 3,600 Lbf or 72" Free Fall	72" Free fall 2754.9 Lbf	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Harness Shall Not Release Test Torso	Did Not Release	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Remain Suspended for \geq 5 Minutes	5 Minutes	Pass
	Dynamic Performance Dorsal D-ring (Head First)	Angle at Rest \leq 30°	22.2°	Pass
	Dynamic Performance Dorsal D-ring (Head First)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
ANSI Z359.11-2021 4.3.6	Fall Arrest Indicator Test (Dorsal D-ring)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
ANSI Z359.11-2021 4.3.6	Fall Arrest Indicator Test (Dorsal D-ring)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass
ANSI Z359.11-2021 4.3.6	Fall Arrest Indicator Test (Dorsal D-ring)	At Least One Fall Arrest Indicator Shall Deploy	Visibly and Permanently Deployed	Pass

Conclusion

Based upon the samples provided to the Lab:
 FallTech P/N 7073BSM Rev. G meets the requirements of ANSI Z359.11-2021

Report Signatories and Approval

Lab Quality Manager		Date	8/19/2021
Witnessed by	Not Required	Date	N/A