

# Declaration of Conformity

In Accordance with ANSI/ISEA 125-2014 and ANSI/ASSP Z359.7-2019



Alexander Andrew, Inc. 1306 S. Alameda St Compton, CA 90221 (800) 719-4619

Declaration #

BC1020140

Declaration Date

10/7/2021

Tested Item #

8123BQCM

**FT-One FBH 3D Construction Belted, Medium, QC Legs and Chest**

**Additional Items Conforming Under this Declaration:**

8123BQCXS	8123BQCXL	8124BQCXS	8124BQCL	8124BQC3X
8123BQCS	8123BQC2X	8124BQCS	8124BQCXL	
8123BQCL	8123BQC3X	8124BQCM	8124BQC2X	

Alexander Andrew, Inc. declares that the product(s) listed above is in conformity with the requirements of the following product standard(s):

**CSA Z259.10-2018**

**Conformity Assessment Method in accordance with ANSI/ISEA 125-2014**

Level 1

Level 2

Level 3

**Level 1:** FallTech Lab  
Outside the Scope of  
ISO/IEC Standard 17025:2005

**Level 2:** FallTech Lab  
Within the Scope of  
ISO/IEC Standard 17025:2005

**Level 3:** Independent 3rd Party Lab  
accredited to  
ISO/IEC Standard 17025:2005

Supporting  
Documentation

PC-2370

**Authorized Signature**

Name

Zachary Winters

Title

Engineering Manager

Date

10/7/2021



International Accreditation Service, Inc  
3060 Saturn St, Ste 100  
Brea, CA 92821 +1 562-364-8201

FallTech Lab - TL-594  
ISO/IEC 17025:2017  
Alexander Andrew Inc dba FallTech

## FallTech Test Report

<b>Test Report No.</b>	PC-2370	<b>Rpt. Date</b>	9/23/2021	<b>Rpt. Rev</b>		<b>Rev Date</b>	
<b>Report Prepared For</b>	FallTech						
<b>Initiated By</b>	Dan Redden	<b>Test Specification(s)</b>	CSA Z259.10-18: 6.2.2.1, 6.2.2.5, 6.2.6				
<b>Part No.</b>	8123BQCM	<b>Part No. Revision</b>	A				
<b>Part Description</b>	FT-One FBH 3D Construction Belted, Medium, QC Legs and QC Chest						
<b>Test Request No.</b>	PC-2370	<b>Date Complete</b>	9/22/2021				
<b>Test Operator(s)</b>	Yesbet Sierra / Jay Sponholz						

### Material/Sample Identification

Sample ID	Description
5783566	FT-One FBH 3D Construction Belted, Medium, QC Legs and QC Chest
5783569	FT-One FBH 3D Construction Belted, Medium, QC Legs and QC Chest
5783529	FT-One FBH 3D Construction Belted, Medium, QC Legs and QC Chest
5783548	FT-One FBH 3D Construction Belted, Medium, QC Legs and QC Chest

### Test Summary

Test Specification	Test Criteria	Test Result	Pass/Fail	
CSA Z259.10-18 6.2.2.1.1	Drop Test Class A Dorsal D-ring (Feet First)	Peak Impact $\geq$ 3,600 Lbf or 39.4" Free Fall	4568.4 lbs. Fall Height 30"	Pass
	Drop Test Class A Dorsal D-ring (Feet First)	Test Mass Remain Suspended for: $\geq$ 2 Minutes	2 Minutes	Pass
	Drop Test Class A Dorsal D-ring (Feet First)	All Connectors remain connected	All Connected	Pass
	Drop Test Class A Dorsal D-ring (Feet First)	Angle at Rest = $\leq$ 30°	6.4°	Pass
	Drop Test Class A Dorsal D-ring (Feet First)	Activate Fall Arrest Indicator	Visibly and Permanently Deployed	Pass
	Drop Test Class A Dorsal D-ring (Feet First)	Harness Stretch $\leq$ Manufactures Stated Value (18")	12.3"	Pass
CSA Z259.10-18 6.2.2.1.2	Drop Test Class A Dorsal D-ring (Head First)	Peak Impact $\geq$ 3,600 Lbf or 39.4" Free Fall	3373.3 lbs. Fall Height 39.4"	Pass
	Drop Test Class A Dorsal D-ring (Head First)	Test Mass Remain Suspended for: $\geq$ 2 Minutes	2 Minutes	Pass
	Drop Test Class A Dorsal D-ring (Head First)	All Connectors remain connected	All Connected	Pass
	Drop Test Class A Dorsal D-ring (Head First)	Activate Fall Arrest Indicator	Visibly and Permanently Deployed	Pass

### FallTech Test Report

<b>Test Report No.</b>	PC-2370	<b>Rpt. Date</b>	9/23/2021	<b>Rpt. Rev</b>		<b>Rev Date</b>	
<b>Report Prepared For</b>	FallTech						
<b>Initiated By</b>	Dan Redden	<b>Test Specification(s)</b>	CSA Z259.10-18: 6.2.2.1, 6.2.2.5, 6.2.6				
<b>Part No.</b>	8123BQCM	<b>Part No. Revision</b>	A				
<b>Part Description</b>	FT-One FBH 3D Construction Belted, Medium, QC Legs and QC Chest						
<b>Test Request No.</b>	PC-2370	<b>Date Complete</b>	9/22/2021				



#### Test Summary (Continued)

Test Specification	Test Criteria		Test Result	Pass/Fail
CSA Z259.10-18 6.2.2.5	Drop Test Class P Positioning Connectors	Peak Impact $\geq$ 3,600 Lbf or 39.4" Free Fall	6251.9 lbs. Fall Height 39.4"	Pass
	Drop Test Class P Positioning Connectors	Test Mass Remain Suspended for: $\geq$ 2 Minutes	2 Minutes	Pass
	Drop Test Class P Positioning Connectors	All Connectors remain connected	All Connected	Pass
CSA Z259.10-18 6.2.6	Fall Arrest Indicator Static	Load to 900 lbs. or Indicator deploys Whichever occurs first	542.2 lbs.	Pass
	Fall Arrest Indicator Static	Verify Fall Arrest Indicator has activated	Visibly and Permanently Deployed	Pass

#### Conclusion

Based upon the samples provided to the Lab:  
 FallTech P/N 8123BQCM Rev. A meets the requirements of CSA Z259.10-18

#### Report Signatories and Approval

Lab Quality Manager		Date	9/23/2021
Witnessed by	Bob Howey (Element) 	Date	10-1-21

